


M & T Pump Station Intake Second Physical Model



Prepared by
A. L. Cox, J. L. Woidt and C. I. Thornton
October 2011
Colorado State University

Introduction

- Since prior 2007 testing, bar migration and sedimentation at the current pump intake has continued
- TetraTech, Inc., working in coordination with Ducks Unlimited, Inc., funded a second physical model study in 2010
- Evaluate hydraulic, morphologic, and sedimentation patterns near the following sites:
 1. Current pump intake location
 2. Proposed Alternative 1 site, ~2,200 ft downstream of the current pump-intake location
 3. Proposed Alternative 2 site, ~3,500 ft downstream of the current pump-intake location
- Three channel configurations:
 1. Current field conditions (Baseline)
 2. Gravel-stockpile on the west floodplain
 3. Realigned section of the east bank with revetment for Proposed Alternative 2 site



Locus map illustrating the study reach


Physical Model

- 10,300-ft reach of the Sacramento River
- 1:100 Undistorted Froude-scale
- Sediment Scaling
 - Ratio of Shields parameter to critical Shields parameter
 - Ratio of flow velocity to critical flow velocity
 - Rouse number
- Scaled sediment sizing for mobile material within the channel
 - Model bed material $d_{50} = 0.15$ mm
 - Prototype bed material $d_{50} = 40$ mm
- 3 scaled discharges evaluated:
 - 145,000-cfs (10-yr recurrence interval flow)
 - 90,000-cfs (bankfull discharge)
 - 10,000-cfs (50% exceedance flow)

Variable	Symbol	Dimension	Similitude Relationship
Length	L	L	$L_p = 100 \cdot L_m$
Time	T	T	$T_p = 10 \cdot T_m$
Velocity	V	L/T	$V_p = 10 \cdot V_m$
Shear Stress	τ	M/LT ²	$\tau_p = 100 \cdot \tau_m$
Discharge	Q	L ³ /T	$Q_p = 100,000 \cdot Q_m$
Unit Discharge	q	L ² /T	$L_p = 1,000 \cdot L_m$

Note: Subscripts m and p denote model and prototype, respectively

Froude-scale conversions




Model extents identified on aerial photograph of the Sacramento River

Physical Model

Model construction started in the summer of 2010:

- 30 E-W soil-cement cross sections
- 1 N-S cross-section defining the downstream boundary
- Very fine sand material to model bed and floodplain sediment
- Cohesive soil to model cohesive stream banks along downstream east bank
- Mesh baffle to provide uniform flow entrance conditions
- Downstream gate to control backwater
- Sediment feed upstream of the test reach
- Installation of artificial trees and canopy

Summary of Variables		
Variable	Prototype	Model
Hydraulic		
Elevation, Length	110 ft	1.10 ft
Flow Depth	25.0 ft	0.25 ft
Discharge	145,000 cfs	1.45 cfs
Flow Velocity	6.0 ft/s	0.6 ft/s
Shear Stress	2.0 psf	0.02 psf
Sediment		
Sediment d_{50}	40 mm	0.15 mm
Time	22.9 hr	1 hr



Identified Sediment Locations

Test Matrix

- Baseline
 - 10,000 cfs (8.5 hrs)
 - 90,000 cfs (143 hrs)
 - 145,000 cfs (7.5 hrs)
- Gravel Stockpile
 - 145,000 cfs (7.5 hrs)
- Realigned Bank
 - 10,000 cfs (4 hrs)
 - 90,000 cfs (148 hrs)
 - 145,000 cfs Test 1 (8 hrs)
 - 145,000 cfs Test 2 (8 hrs)
 - bed reset to original realigned-bank elevations between Test 1 and Test 2
 - 145,000 cfs Test 3 (8 hrs)
 - Bed elevations not reset between Test 2 and Test 3 resulting in 16 total hours of 145,000-cfs testing




Typical Testing Program

- Testing program:
 - Measure bed elevation before testing
 - Establish model discharge and backwater
 - “Begin” testing
 - Measure flow velocities
 - 10,000-cfs testing for ~8-hours
 - 90,000-cfs testing for ~140-hours
 - 145,000-cfs testing for ~8-hours
 - Slowly decrease the discharge and drain the model
 - Measure bed elevation after testing





10,000-cfs Baseline Testing

Data Collection Locations




Comparison of Second Physical Model with the 2007 Model




Baseline Velocity Distribution of 2010 Model:
90,000-cfs Testing

Baseline Velocity Distribution of 2007 Model:
90,000-cfs Testing

Baseline Testing: 90,000-cfs




**90,000-cfs Baseline
Flow Velocity Distribution**




**Elevation Difference between Post-90,000-cfs
Baseline Testing and Pre-10,000 cfs**

Baseline Testing: 145,000-cfs




**145,000-cfs Baseline
Flow Velocity Distribution**



**Elevation Difference between Post-145,000-
cfs Baseline Testing and Pre-10,000 cfs**

Baseline Testing Summary

- Current Pump Location
 - Continued trends of sedimentation near the pump
 - Agg. up to 5 ft (from 145,000-cfs test)
 - Lower flow velocities compared to the main channel promoting sedimentation
- Proposed Alternative 1 Site
 - Agg. up to 5 ft in the main channel (from 145,000-cfs test)
 - 2 to 5-ft strip of deg. along the bank (from 145,000-cfs test)
- Proposed Alternative 2 Site
 - Negligible agg. and deg. (from 145,000-cfs test)
- WPCP Outfall
 - Negligible agg. and deg. (from 145,000-cfs test)



Elevation Difference between Post-145,000-cfs Baseline Testing and Pre-10,000 cfs


Hydraulic Modeling – Gravel Stockpile

- Prototype Gravel Stockpile:
 - 1000' Long x 300' Wide x 10' High
 - 1.5H:1V Side Slopes
 - To be constructed of dredged channel material from maintenance of current pump station
- Model Gravel Stockpile:
 - Scaled down prototype dimensions
 - Superimposed on baseline configuration topography
 - Used mobile sediment to construct
 - Significantly inundated only at model 145,000-cfs flow




Constructed model Gravel Stockpile

Gravel Stockpile: Comparison




**145,000-cfs with Stockpile
Flow Velocity Distribution**




**145,000-cfs Baseline
Flow Velocity Distribution**

Gravel Stockpile: Comparison



Post-145,000-cfs Gravel-stockpile Testing Elevation Difference from Initial Gravel-stockpile Elevations




Post-145,000-cfs Baseline Testing Elevation Difference from Post-10,000-cfs Baseline

Hydraulic Modeling – Realigned Bank


- Prototype Bank realignment
 - Straightening of East bank near Proposed Alternative 1 Site
 - Riprap along east bank from current pump intake to downstream of Proposed Alternative 1 Site
 - Pea-gravel used to model riprap
- Proposed Alternative 1 Site is no longer a potential relocation site with the bank realignment



Bank Realignment Testing: 90,000-cfs




**Realigned Bank 90,000-cfs
Flow Velocity Distribution**




**Elevation Difference between Post-90,000-cfs
Realignment Testing and Pre-10,000 cfs**

Bank Realignment Testing: 145,000-cfs




**Realigned Bank 145,000-cfs
Flow Velocity Distribution**




**Elevation Difference between Post-145,000-cfs
Realignment Testing and Pre-10,000 cfs**

Bank Realignment: Comparison




**Realigned Bank 145,000-cfs
Flow Velocity Distribution**




**Baseline 145,000-cfs Flow
Velocity Distribution**

Bank Realignment: Comparison




Post-145,000-cfs Realigned-bank Test 1
 Elevation Difference from Pre-10,000-cfs Test




Post-145,000-cfs Baseline Testing Elevation
 Difference from Post-10,000-cfs Baseline

Bank Realignment: Comparison




**Realigned Bank 145,000-cfs Post-Test 2
 Bed Elevation Difference from Pre-Test 2 (8 hrs)**




**Realigned Bank 145,000-cfs Post-Test 3
 Bed Elevation Difference from Pre-Test 2 (16 hrs)**

Bank Realignment: Comparison



**Realigned Bank 145,000-cfs Post-Test 3
 Bed Elevation Difference from Pre-Test 3 (8 hrs)**




**Realigned Bank 145,000-cfs Post-Test 3
 Bed Elevation Difference from Pre-Test 2 (16 hrs)**

Bank Realignment Testing Summary

- Hydraulic and sedimentation trends varied from Baseline and Gravel-stockpile trends
- Higher main-channel flow velocities compared to Baseline Testing
- Current pump location
 - Agg. up to 5 ft just northwest of current pump-intake (from 145,000-cfs test)
 - Negligible velocity difference compared to Baseline conditions
- Proposed Pump Alternative Location #1
 - Deg. up to 2 ft at 10,000 cfs and 90,000 cfs
 - Agg. up to 5 ft immediately upstream (from 145,000-cfs test)
 - Increased flow velocities compared to baseline conditions at 145,000 cfs
- Proposed Pump Alternative Location #2
 - Negligible agg. and deg. (from 145,000-cfs test)
 - Increase in velocity of main channel compared to Baseline
- WCPC Outfall
 - Agg. immediately upstream
 - Deg. immediately downstream
 - Measured upstream agg. suggests that a maximum of 2 ft of aggradation could be expected at the WPCP outfall


Summary Chart

Aggradation/Degradation at 145,000 cfs




Summary Charts


Baseline Testing



Gravel Stockpile Testing



Realigned Bank Testing



Conclusions from Hydraulic Model

- Continued sedimentation up to 5 ft is expected with existing field conditions near the current pump-intake location
- Construction of the gravel stockpile on the west floodplain would have an insignificant effect on the hydraulics and erosion and sedimentation trends within the study reach
- The Proposed Alternative 1 site may be suitable for pump-intake relocation because the model predicted degradation up to 5 ft near the Proposed Alternative 1 site for both the existing field conditions and with the construction of the gravel stockpile
- The Proposed Alternative 2 site may be suitable for pump-intake relocation because
 - The model indicated minimal aggradation and degradation near the Proposed Alternative 2 site
 - The site experienced the most consistent bed elevations with minimal aggradation and degradation in the surrounding areas compared to the other evaluated pump location sites
- The model indicated aggradation immediately upstream of the WPCP outfall and degradation immediately downstream of the WPCP outfall with the bank realignment for the Proposed Alternative 2 site
 - The measured upstream aggradation suggests that a maximum of 2 ft of aggradation could be expected at the WPCP outfall.